

MIAOLI PHASE 1 • SPEC SHEET

Power plant to rack. Compute, delivered whole.

Star Counter builds and operates high-density, liquid-cooled AI data centers in Taiwan. Miaoli Phase 1 combines on-site gas generation, 45 °C warm-water liquid cooling and prefabricated modules, designed for whole-rack NVIDIA Vera Rubin NVL72 deployments at 188–227 kW per rack.

5 MW

Phase 1 IT load

24 racks

VR NVL72

1,728

GPUs

1.11

Annual PUE, design

2028 Q1

Target go-live

★ Engagements

COLOCATION

Liquid-cooled colocation

You buy the racks; we provide power, liquid loops, space and 24 × 7 operations. Billed on contracted power, reference from US\$200 / kW • month, 5 + 5 yr.

BARE-METAL RACK

Bare-metal rack lease

Star Counter owns and operates whole VR NVL72 racks and delivers them as bare metal. Quoted by racks, term and prepayment.

INFERENCE • PLANNED

Inference API

Token-metered inference on open models with data kept in Taiwan. Pre-registration open.

★ Campuses

Miaoli


50 MW • on-site gas gensets in parallel • dual 24 kV feeds

Phase 1 (5 MW) design complete, tendering in preparation

Kaohsiung

50 MW • Taipower grid

Planning; reuses the Miaoli module design



Reserve Phase 1 capacity

Send rack count, per-rack power, term and target go-live. Sales and engineering will reply together with a deployment plan.

sales@starai.tw


starai.tw

★ Phase 1 design values

VR NVL72 racks	24
GPUs	1,728
IT load Max-Q / Max-P	4,962 / 5,898 kW
Facility peak demand	5,811 kW
PUE peak / annual	1.171 / ≈1.11
Liquid-cooled share	≈ 92%
Supply water	45 °C
Support racks	18 × 25 kW
Battery ride-through	LFP · 5 min
Prefabricated modules	19

★ DR4N3 distributed redundancy

Every IT module is fed by two different power blocks, never shared within a pod. Each block runs near 62% in normal operation and no more than 98% if any one fails.



★ Power and cooling

Power Gas gensets / Taipower → 24 kV RMU → 2,500 kVA × 4 → UPS + LFP → A/B busway 1,600 A × 12 → VR NVL72

Cooling Cold plates, 100% liquid → rack loop 45 °C → CDU 2.5 MW × 2 per pod → adiabatic dry coolers 8 + 1; plant water via plate HX 2 × 50% as backup

★ Configurations

1 rack 72 GPU 188 / 227 kW	Half pod 288 GPU 752 / 908 kW	Full pod 576 GPU 1,504 / 1,816 kW	All of Phase 1 1,728 GPU 4,512 / 5,448 kW
---	--	--	--

★ From inquiry to go-live

01	02	03	04
Capacity and spec fit	Site visit and review	Contract and reservation	Install, accept, hand over
≈ 2 weeks	≈ 4 weeks	From signing	From Q1 2028

Values are design-stage results; contract and acceptance govern. Images are 3D renderings, not photographs. GPU figures follow NVIDIA public data; the OEM spec sheet governs.

Reserve Phase 1 capacity

Send rack count, per-rack power, term and target go-live. Sales and engineering will reply together with a deployment plan.

sales@starai.tw
starai.tw